


HAMILTON CONSERVATION AUTHORITY


SALTFLEET CONSERVATION AREA STONEY CREEK SC-8 520 GREEN MOUNTAIN ROAD EAST

OCTOBER 2024



	Sheet Number	Sheet Title
	1	GENERAL GRADING PLAN
	2	ARCHAEOLOGY PLAN
	3	MAIN POND GRADING PLAN 1
	4	MAIN POND GRADING PLAN 2
	5	MAIN POND GRADING PLAN 3
	6	MAIN POND GRADING PLAN 4
Hamilton	7	MAIN POND CROSS SECTIONS 1
Conservation	8	MAIN POND CROSS SECTIONS 2
	9	POND & WETLAND DETAILS
Authority	10	MAIN POND OUTLET
Z	11	MAIN POND OUTLET DETAILS
	12	EROSION & SEDIMENT CONTROL
A Healthy Watershed for Everyone	13	EROSION & SEDIMENT CONTROL DETAILS
	14	PLANTING PLAN
	15	SEEDING PLAN
	16	PLANTING PLAN DETAILS

DRAWING LIST



SU	RVEY COMPLETE	D ON AU	IG 28, 2019
4	20241025	EEG	ISSUED FOR TENDER
3	20241018	EEG	REVISED BASED ON HCA COMMENTS
2	20240208	EEG	REVISED BASED ON HCA COMMENTS
1	20201204	EEG	REVISED BASED ON HCA COMMENTS
No.	DATE	BY	REVISIONS
	TE: October 25, 24 ALE: RIZONTAL - 1:750	024	REVISIONS PROFESSION E. GAZUNDAM PROFESSION E. GAZUNDAM PROFESSION PROFESION PROFESSION PROFESSION PROFESSION PROFESSION PROFES
100			EL SOLUTIONS TEAM OF
			Hamilton Conservation Authority
	A He	ealthy	Watershed for Everyone
			CONSERVATION AREA EY CREEK (SC-8)
	GEN	ERA	L GRADING PLAN

DESIGN	PROJECT No.
EEG	19028
CHECKED	SHEET No.
EG	1



GREEN MOUNTAIN ROAD EAST

PART 5


PART

TRIBUTARY 1

DITCH CENTRELINE



PROPERTY LINE EXISTING CULVERT EXISTING TOP OF BANK EXISTING BOTTOM OF BANK EXISTING CREEK CENTRELINE



Meters

Conservation Authority



PROJECT No.

SHEET No.

19028

2

CONSULTANT Waters Consultant Solutions TEAM


REVISIONS


REVISED BASED ON HCA COMMENTS


REVISED BASED ON HCA COMMENTS


REVISED BASED ON HCA COMMENTS


ISSUED FOR TENDER












		N		···				Helle,	دی ح								
FLOOD ELEVATI	ON - 193.00	D	\backslash						X	- 196							
										195							
							1/1/,	<u>U</u>		194							
			ALLA							193							
										192							
										- 191							
										+ 190							
										189							
										- 188							
)	130	14	0	15	50	1	60	1	70	⊥ 187							
										- 201							
										- 200							
										- 199							
			PROF	POSED FILI	L PLACE	EMENT —	7										
										- 198							
					·'n.	$\sum_{i=1}^{n}$			<u>, , , , , , , , , , , , , , , , , , , </u>	- 197							
	-				X					196							
						CILL				195							
	$ \rightarrow $	\square	/							- 194							
			<u>> мах</u>	x 3:1 Slope	Ξ					- 193							
				ROUND						- 192							
				ROUND						- 191							
										- 190							
			f														
										100							
										189							
110	12	0	13	30	14	40	1	50	160	189 188 188							
110	12	0	13	30	14	40	1	50	200 199 198	4 2	20241025 20241018 20240208 20201204 DATE	EEG EEG EEG EEG BY	REV	ISED B ISED B ISED B	ASED ON ASED ON ASED ON REVISIOI		MENTS MENTS
110	12	0	13	30	14	40	1	50	200 199 198 197	4 3 2 1	20241018 20240208 20201204	EEG EEG EEG	REV	ISED B ISED B ISED B	ASED ON ASED ON ASED ON REVISIOI	HCA COM HCA COM HCA COM NS	MENTS MENTS
110		0		30	14	40	1	50	200 199 198 197 196	4 3 2 1	20241018 20240208 20201204 DATE	EEG EEG EEG BY	REV	ISED B ISED B ISED B	ASED ON ASED ON ASED ON REVISIOI	HCA COM HCA COM HCA COM NS	MENTS MENTS
110				30	14	40		50	200 199 198 197 196 195	4 3 2 1 No. DATE:	20241018 20240208 20201204 DATE October 25,	EEG EEG EEG BY	REV	ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION PROFE E. GAZ	HCA COM HCA COM HCA COM NS SSIOVIZ	MENTS
110				30				50	200 199 198 197 196	4 187 187 4 3 2 1 No. DATE: SCALE: HORIZO	20241018 20240208 20201204 DATE October 25,	EEG EEG EEG BY	REV	ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION PROFE E. GAZ	HCA COM HCA COM HCA COM NS SSIOVIZ	MENTS
110				30		40 40 3:1 SLOPE		50	200 199 198 197 196 195	4 3 2 1 No. DATE: SCALE: HORIZC VERTIC	20241018 20240208 20201204 DATE October 25,	EEG EEG EEG BY	REV	ISED B/ ISED B/ ISED B/	ASED ON ASED ON ASED ON REVISIOI	HCA COM HCA COM HCA COM NS SSIOVIZ	MENTS
110				30				50	200 199 198 197 196 195 194	4 187 187 4 3 2 1 No. DATE: SCALE: HORIZO	20241018 20240208 20201204 DATE October 25,	EEG EEG BY 2024	REV REV	ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION PROFE E. GAZ	HCA COM HCA COM NS SS I OVIE	MENTS
110				30				50	200 199 198 197 196 195 194 193	4 3 2 1 No. DATE: SCALE: HORIZC VERTIC	20241018 20240208 20201204 DATE October 25,	EEG EEG BY 2024	REV REV	ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION PROFE E. GAZ	HCA COM HCA COM NS SS I OVIE	MENTS
110				30				50	200 199 198 197 196 195 194 193 192	4 3 2 1 No. DATE: SCALE: HORIZC VERTIC	20241018 20240208 20201204 DATE October 25,	EEG EEG BY 2024	REV REV	ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION PROFE E. GAZ	HCA COM HCA COM NS SS I OVIE	MENTS
				30				50	200 199 198 197 196 195 194 193 192 191	4 3 2 1 No. DATE: SCALE: HORIZC VERTIC	20241018 20240208 20201204 DATE October 25,	EEG EEG BY 2024	REV REV	ISED B/ ISED B/ ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION E. GAZ C. N S T E /		MENTS MENTS MENTS
				30				50	200 199 198 197 196 195 194 193 192 191 191	4 3 2 1 No. DATE: SCALE: HORIZC VERTIC	20241018 20240208 20201204 DATE October 25,	EEG EEG BY 2024	REV REV	ISED B/ ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION E. GAZ E. GAZ NCE N S T E Iamili		MENTS MENTS MENTS
				30				50	200 199 198 197 196 195 194 193 192 191 191 190 189 188	4 3 2 1 No. DATE: SCALE: HORIZC VERTIC	20241018 20240208 20201204 DATE October 25,	EEG EEG BY 2024	REV REV	ISED B/ ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION E. GAZ C. N S T E /		MENTS MENTS MENTS
						3:1 SLOPE			200 199 198 197 196 195 194 193 192 191 190 189	4 3 2 1 No. DATE: SCALE: HORIZC VERTIC	20241018 20240208 20201204 DATE October 25, DNTAL - 1:400 CAL - 1:100		REV REV	ISED B/ ISED B/ ISED B/ ISED B/ ISED B/ ISED B/	ASED ON ASED ON REVISION E. GAZ C. C. C	HCA COM HCA COM HCA COM NS SSIQUE CENDAM	MENTS MENTS MENTS OUT OT LTD.
	EXIST				MAX 3	3:1 SLOPE			200 199 198 197 196 195 194 193 192 191 192 191 190 189 188 188	4 188 187 4 3 2 1 No. DATE: SCALE: HORIZC VERTIC CONSU	20241018 20240208 20201204 DATE October 25, DNTAL - 1:400 CAL - 1:100	EEG EEG BY 2024		ISED B/ ISED S/ ISED S	ASED ON ASED ON ASED ON REVISION E. GAZ C C C C C C C C C C C C C C C C C C C		MENTS MENTS MENTS OUTRER OUTRE OUTRER OUTREN
	EXIST				MAX 3	3:1 SLOPE			200 199 198 197 196 195 194 193 192 191 192 191 190 189 188 188	4 3 2 1 No. DATE: SCALE: HORIZC VERTIC CONSU	20241018 20240208 20201204 DATE October 25, DNTAL - 1:400 CAL - 1:100			ISED B/ ISED B	ASED ON ASED ON ASED ON REVISION E. GAZ C. C. C. C. C. C. C. C. C. C. C. C. C. C. C. C. C. C	HCA COM HCA COM HCA COM HCA COM NS SS I QV42 QUANDAM 25, 424 OF OF OF OF OT OT OT OT OT OT OT OT OT OT OT OT OT	
	EXIST				MAX 3	3:1 SLOPE			200 199 198 197 196 195 194 193 192 191 192 191 190 189 188 188	188 187 187 187 187 187 1	20241018 202008 20201204 DATE October 25, DNTAL - 1:400 CLITANT CENVIRCE A H SALTFL S AIN PO	EEG EEG BY 2024 2024 2024 2024 2024 2024 2024 202			ASED ON ASED ON ASED ON REVISION E. GAZ AGA ASED ON REVISION E. GAZ AGA ASED ON E. GAZ AGA ASED ON E. GAZ AGA ASED ON E. GAZ ASE ASE CON CON CE CON CE CON CON CE CON CON CE CON CON CE CON CON CON CE CON CON CON CON CON CON CE CON CON CON CON CON CON CON CON CON CON	HCA COM HCA COM HCA COM HCA COM NS SS I QV42 QUANDAM 25, 424 OF OF OF OF OT OT OT OT OT OT OT OT OT OT OT OT OT	n NENTS MENTS MENTS NER OLIVER OLIVER NER NS 1
	EXIST				MAX 3	3:1 SLOPE			200 199 198 197 196 195 194 193 192 191 192 191 190 189 188 188	 188 187 4 3 2 1 No. DATE: SCALE: HORIZO VERTIO CONSU S M	20241018 202008 20201204 DATE October 25, DNTAL - 1:400 CLITANT CENVIRCE A H SALTFL S AIN PO	EEG EEG BY 2024 2024 2024 2024 2024 2024 2024 202		ISED B/ ISED S/ ISED S	ASED ON ASED ON ASED ON REVISION E. GAZ AGA ASED ON REVISION E. GAZ AGA ASED ON E. GAZ AGA ASED ON E. GAZ AGA ASED ON E. GAZ ASE ASE CON CON CE CON CE CON CON CE CON CON CE CON CON CE CON CON CON CE CON CON CON CON CE CON CON CON CON CE CON CON CON CON CON CE CON CON CON CON CON CON CON CON CON CON		n NENTS MENTS MENTS NER OLIVER OLIVER NER NS 1



LEGEND:

- 201

- 200

- 199

198

- 197

PROPOSED FILL PLACEMENT


EXISTING GROUND


120


AREA OF CUT

AREA OF FILL

EXISTING GROUND PROPOSED GROUND








RIVERSTONE

D50 = 200mm ____ DEPTH - 2 x D50 = 400mm ___

193.15 192.61

0+100




SHEET No.

8

CHECKED

EG



CHANNEL OPENING NOTES:

AFTER STABILIZATION OF THE BANKS IS CONFIRMED, FLOW IS TO BE REINITIATED INTO CHANNEL UNDER SUPERVISION OF THE PROJECT FLUVIAL GEOMORPHOLOGIST. 2. CONTRACTOR SHALL ENSURE THAT CHANNEL REMAINS ISOLATED FROM FLOWS UNTIL THE OUTLET AND CHANNEL CONSTRUCTION WORK IS COMPLETE.

AREA STABILIZATION:

EROSION CONTROL BLANKETS ARE TO BE PLACED TO CONTROL EROSION AFTER SEEDING. ECB TO BE COIR 400 BLANKET OR APPROVED EQUIVALENT AND INSTALLED AS PER MANUFACTURER'S SPECIFICATIONS.

CONSTRUCTION SUPERVISION:

CONSTRUCTION SUPERVISION TO BE COMPLETED BY HCA STAFF WITH TECHNICAL SUPPORT FROM WATER'S EDGE AND SHALL BE AVAILABLE DURING ALL PHASES OF CONSTRUCTION AND IN-WATER WORKS.

GENERAL CREEK NOTES

STONEY CREEK IS CLASSIFIED AS A COLDWATER SYSTEM WITH AQUATIC HABITAT WITHIN THE CONSTRUCTION AREA. AS A RESULT OF THESE CHARACTERISTICS A CONSTRUCTION TIMING WINDOW THAT PROHIBITS IN-WATER CONSTRUCTION ACTIVITIES BETWEEN SEPT 30TH AND JULY 15TH MUST BE RESPECTED.

2. ALL CHANNEL ACTIVITIES MUST BE COMPLETED IN THE DRY USING CONVENTIONAL DAM AND PUMP METHODS (IN-STREAM PLUG AND BYPASS PUMPING), OR A COMBINATION OF DIVERSION PIPING AND DAM AND PUMP METHODS.

B. NEW BANKS TO BE INTEGRATED INTO EXISTING BANK HEIGHT IN BOTH UPSTREAM AND DOWNSTREAM DIRECTIONS AND BE KEYED IN FOR 2-5M.

4. ANY FILL MATERIAL IS TO BE PLACED IN LIFTS COMPACTED TO 95% SPD AND CONFIRMED WITH COMPACTION TESTING UNLESS SPECIFIED.

5. PROPER EROSION AND SEDIMENT CONTROL MEASURES TO BE USED AT ALL LOCATIONS TO PREVENT SEDIMENT FROM ENTERING WATER COURSE.

6. BANKS TO BE REVEGETATED AS PER THE DESIGN DRAWINGS WITH COIR FABRIC, SEED AND STABILIZED WITH NATIVE VEGETATION AS PER SPECIFICATIONS.

. CONTRACTOR TO RESTORE ANY DAMAGED AREAS TO THE EXISTING CONDITION OR TO THE SATISFACTION OF THE CLIENT AND CONTRACT ADMINISTRATOR.

FISHERIES MITIGATION NOTES

FISH ARE TO BE COLLECTED AND RELOCATED FROM THE CONSTRUCTION AREA PRIOR TO THE BYPASS PUMPING/DIVERSION PIPING AND SUBSEQUENT CHANNEL DEWATERING, AND RELEASED ALIVE IMMEDIATELY DOWNSTREAM. ANY FISH COLLECTION AND RELOCATION SHALL BE COMPLETED BY A QUALIFIED FISHERIES PROFESSIONAL UNDER A SCIENTIFIC COLLECTORS PERMIT, ISSUED BY THE MINISTRY OF NATURAL RESOURCES.

THE CONTRACTOR WILL BE RESPONSIBLE FOR ENSURING THE CONTINUOUS OPERATION OF THE BYPASS PUMPING/DIVERSION PIPING, TO ENSURE THAT THE WATER FLOW WILL BE MAINTAINED CONTINUOUSLY DOWNSTREAM OF THE WORK AREA (DURING ALL STAGES OF THE WORK), AND DISCHARGED BACK INTO THE CHANNEL USING A DIFFUSER/DISSIPATER TO ENSURE THAT THE RETURNING WATER DOES NOT SCOUR OR ERODE THE STREAMBED AND BANKS. BYPASS PUMPING/DIVERSION PIPING IS TO BE ADEQUATELY SIZED TO CONTROL A RANGE OF ANTICIPATED CREEK FLOWS. THE ANTICIPATED BASE FLOW RATE WITHIN THE CHANNEL DURING THE CONSTRUCTION TIMING WINDOW IS UNKNOWN AT THIS TIME.

FISHERIES TIMING WINDOW: THERE SHALL BE NO IN-WATER WORK OR ACTIVITY FROM SEPTEMBER 30^{TH} TO JULY 15^{TH} .

ENVIRONMENTAL NOTES

REFUELLING ACTIVITIES SHOULD BE CONDUCTED IN AN ENVIRONMENTALLY RESPONSIBLE MANNER. THIS INCLUDES KEEPING THE FUELLING OPERATIONS 30 M SETBACK FROM THE WATER'S EDGE, DRAINAGE PATHWAY OR UNLESS OTHERWISE DIRECTED BY THE CONTRACT ADMINISTRATOR. SPILL KITS AND SUFFICIENT AMOUNT OF SORBANT MATERIAL SHOULD BE AVAILABLE ON THE FUEL OR SERVICE VEHICLES.

2. ANY PART OF EQUIPMENT ENTERING THE WATER SHOULD BE FREE OF FLUID LEAKS AND EXTERNALLY CLEANED AND DEGREASED TO PREVENT ANY DELETERIOUS SUBSTANCES FROM ENTERING THE WATER.

8. ANY SPILLS RESULTING FROM REFUELLING OPERATIONS, HYDRAULIC LEAKS, MAINTENANCE ETC. MUST BE REPORTED IMMEDIATELY TO THE SPILLS ACTION CENTRE AND CONTRACT ADMINISTRATOR. THE LOCAL MUNICIPALITY, OWNER OF THE SUBSTANCE AND PERSON IN CONTROL OF THE SUBSTANCE MUST ALSO BE NOTIFIED IMMEDIATELY.

4. ALL MATERIALS AND EQUIPMENT USED FOR THE PURPOSE OF SITE PREPARATION AND PROJECT COMPLETION SHOULD BE OPERATED AND STORED IN A MANNER THAT PREVENTS ANY DELETERIOUS SUBSTANCE (E.G. PETROLEUM PRODUCTS, SILT, DEBRIS, ETC) FROM ENTERING THE WATER.

5. THE AREA OF DISTURBANCE WITHIN THE CHANNEL AND ON THE STREAMBANKS MUST BE KEPT TO A MINIMUM. HEAVY EQUIPMENT TRAFFIC WILL BE RESTRICTED TO ESTABLISHED TRAVEL PATHWAYS.


6. STOCKPILE AND STAGING AREAS SHOULD BE WELL REMOVED FROM THE WATERCOURSE AND CONTAINED BY APPROPRIATE SEDIMENT AND EROSION CONTROLS.

2. SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE INSTALLED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD. THE INSTALLED MEASURES SHOULD BE ROUTINELY INSPECTED TO ENSURE THAT THEY ARE FUNCTIONING AS INTENDED. DISTURBED SOILS SHOULD BE STABILIZED IMMEDIATELY WITH SUITABLE PLANTINGS/SEED/MAT. MAINTENANCE SHOULD CONTINUE UNTIL SUCH TIME AS THE DISTURBED AREAS ARE SUFFICIENTLY STABILIZED THROUGH VEGETATIVE GROWTH.

8. TEMPORARY CROSSING OF THE WATERCOURSE IS PERMITTED WITH A SPAN STRUCTURE. SPECIFIC DETAILS TO BE PROVIDED BY CONTRACTOR

9. WEATHER CONDITIONS SHOULD BE MONITORED TO ADEQUATELY PREPARE THE SITE FOR RAIN EVENTS. IF STORM FLOWS ARE EXPECTED, ALL E&S MEASURES SHALL BE INSPECTED AND REPAIRED.

10. AS CONSTRUCTION ACTIVITIES IN AND AROUND WATER IS CHALLENGING, WITH A SIGNIFICANT POTENTIAL FOR ENVIRONMENTAL EFFECT, IT IS RECOMMENDED THAT THE CONTRACTOR ORGANIZE AN IN-WATER CONSTRUCTION TEAM WHICH WILL CONSIST OF AN ENVIRONMENTAL MONITOR, SUPERVISOR, SELECTED MACHINE OPERATORS AND GENERAL LABOURERS. THIS TEAM WILL BE RESPONSIBLE FOR THE CONSTRUCTION ACTIVITIES WITHIN THE CHANNEL INCLUDING THE CONSTRUCTION OF THE CHANNEL AND RE-GRADING OF THE STREAMBANKS AND FLOODPLAINS.



DATE







A Healthy Watershed for Everyone

SALTFLEET CONSERVATION AREA STONEY CREEK (SC-8)

POND & WETLAND DETAILS

DESIGN	PROJECT No. 19028
CHECKED	SHEET No. 9







4 20241025 EI	EG	ISSUED FOR TENDER
3 20241018 EI	EG REV	ISED BASED ON HCA COMMENTS
2 20240208 EI	EG REV	ISED BASED ON HCA COMMENTS
1 20201204 EI	EG REV	ISED BASED ON HCA COMMENTS
No. DATE B	3Y	REVISIONS
DATE: October 25, 2024		REVISIONS PROFESSION E. GAZENDAM E. GAZENDAM
SCALE: HORIZONTAL - 1:150 VERTICAL - 1:37.5 CONSULTANT		PHA AVCE OF OVITAL
A	3	 Hamilton Conservation Authority
P		
A Hea	Ithy Water	shed for Everyone
		SERVATION AREA REEK (SC-8)
MAI	N PON	D OUTLET
		PROJECT No. 19028
		10020


EG

10



0+395






STONE SIZING GRAD							
700 - 800	5%						
600 - 700	10%						
500 - 600	15%						
400 - 500	20%						
300 - 400	15%						
150 - 300	10%						
< 150	5%						
Granular "B"	20%						
SUM	100%						
ADD ADDITIONAL GRANULAR B TO FILL ANY INTERSTITIAL VOIDS AS NECESSARY							
GRANULAR B MUST BE NEW PIT RUN AND NOT RECYCLED MATERIAL							


4	20241025	EEG		ISSUED FOR	TENDER	
3	20241018	EEG	REVISED BASED ON HCA COMMENTS			
2	20240208	EEG	REVISED BASED ON HCA COMMENTS			
1	20201204	EEG	REVI	SED BASED ON	HCA COMMENTS	
No.	DATE	BY	REVISIONS			
	October 25,	2024	-	E. GAZ	SSIQUE ENGLISEER	
CUN		ate		S C		
	Ű		J	Hamilt Conse Autho	rvation	
	AH	ealthy	Water	shed for E	veryone	
				SERVATI REEK (SC	ON AREA C-8)	
	MAIN	PON	Ο ΟΙ	ITLET C	ETAILS	
DES	IGN EE	G		PROJECT No.	9028	
CHE	CKED	-		SHEET No.	11	


EG


11


STONE SIZING GRADATION 200mm STONE (mm)						
400 - 500	5%					
300 - 400	20%					
200 - 300	25%					
100 - 200	25%					
50 - 100	10%					
0 - 50	5%					
Granular "B"	10%					
SUM	100%					











CONSTRUCTION ACCESS:

ACCESS TO THE CONSTRUCTION SITE WILL BE OFF GREEN MOUNTAIN ROAD EAST. TREES TO BE TRIMMED OR REMOVED FROM ACCESS AS APPROVED BY CONTRACT ADMINISTRATOR AND MUNICIPALITY.

3. SAFETY FENCE TO BE ERECTED AS REQUIRED TO LIMIT PUBLIC ACCESS TO TEMPORARY CONSTRUCTION ACCESS ROAD AND CONSTRUCTION SITE. 4. SITE CONSTRUCTION ACTIVITY WILL INCLUDE THE REPAIR OF THE CREEK ACCESS AND EGRESS AREA AS PER DESIGN.

. UPON COMPLETION OF THE CONSTRUCTION, THE ACCESS WAY IS TO BE REPAIRED TO EXISTING CONDITIONS OR BETTER EXCEPT PERMANENT ACCESS ROUTE. 6. CONTRACTOR TO MEET ON SITE WITH THE CONTRACT ADMINISTRATOR, CONSERVATION AUTHORITY STAFF AND MUNICIPAL STAFF PRIOR TO INITIATION OF CONSTRUCTION.

CONSTRUCTION SEQUENCING AND STAGING NOTES: . CONTRACTOR TO NOTIFY MUNICIPALITY, AGENCIES AND CONTRACT ADMINISTRATOR TWO

(2) DAYS PRIOR TO ACTUAL CONSTRUCTION. 2. THE CONTRACTOR SHALL PROVIDE GENERAL ARRANGEMENT DRAWINGS AND A STAGING

PLAN WITH THE PROPOSED BYPASS METHODOLOGY AND DEMONSTRATE THAT THE APPROACH CAN ADEQUATELY ADDRESS THE ENVIRONMENTAL AND EXISTING SITE CONDITIONS (VARYING FLOW CONDITIONS, CHANNEL CAPACITIES, WET WEATHER RESPONSE).

3. CONSTRUCTION STAGING MUST HAVE REGARD FOR THE ENVIRONMENTAL ASPECTS OF THE PROPOSED CONSTRUCTION. THIS WILL ENSURE THAT AMPLE TIME IS PROVIDED TO ENSURE THE TIMELY ARRIVAL OF REQUIRED EQUIPMENT AND MATERIALS AND THE APPROPRIATE ALLOCATION OF RESOURCES.

4. INSTALL CONSTRUCTION FENCING AND SILT FENCING AS PER SPECIFICATIONS. FENCE TO BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL BE THE LIMIT OF CONSTRUCTION ACTIVITY.

- 5. INSTALL MUD MAT AT ENTRANCES TO SITE AS PER DETAIL D6.
- 6. REMOVE AND DISPOSE OF EXISTING VEGETATION WITHIN THE WORK AREA.
- 7. PLACE DAM & PUMP CONTROLS IN DESIGNATED AREA.
- 8. REMOVE AND STOCKPILE TOPSOIL ALONG PROPOSED BERM.
- 9. SUPPLY AND PLACE ENGINEERED FILL FOR BERM.
- 10. SUPPLY AND PLACE OUTLET STRUCTURES AND OUTFALL STONE.
- 11. GRADE AND SHAPE WETLANDS.
- 12. ALL EXCESS MATERIAL STOCKPILED ON SITE TO BE USED IN BERMS.
- 13. COMPLETE SEEDING AND PLANTING AS PER APPROVED PLANS AND SPECIFICATIONS.
- 14. STABILIZE ALL SLOPES AS NOTED ON PLAN.
- 15.REMOVE DAM & PUMP CONTROLS
- 16. REMOVE ANY EROSION AND SEDIMENT CONTROLS ONCE ALL VEGETATION HAS BECOME SUFFICIENTLY ESTABLISHED.

EROSION AND SEDIMENT CONTROL STRATEGY
1. PRIOR TO COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT A DETAILED SCHEDULE AND WORK PLAN FOR REVIEW AND APPROVAL OF THE CONTRACT ADMINISTRATOR AND EXTERNAL AGENCIES AS REQUIRED, INDICATING HOW HE WILL IMPLEMENT SEDIMENT AND EROSION CONTROLS, AND HOW HE WILL CONTROL/DIVERT CREEK FLOWS AROUND OR THROUGH THE CONSTRUCTION AREA.
2. SEDIMENT AND EROSION CONTROL MEASURES MUST BE IMPLEMENTED PRIOR TO WORK, AND MAINTAINED DURING THE WORK PHASE, TO PREVENT ENTRY OF SEDIMENT INTO THE WATER OR RE-SUSPENDED SEDIMENT.
3. ANY STOCKPILED MATERIALS SHOULD BE STORED AND STABILIZED AT A MAXIMUM 3H:1V SLOPE AND TEXTURED TO REDUCE RUNOFF VELOCITY, LOCATED MINIMUM 30m AWAY FROM THE WATER. EXCESS MATERIAL SHALL BE REMOVED IMMEDIATELY FROM THE CHANNEL AREA AND TEMPORARILY STOCKPILED IN SUITABLE LOCATIONS IDENTIFIED BY THE DESIGN DRAWINGS AND ON-SITE AREAS APPROVED BY THE CONTRACT ADMINISTRATOR.
4. ALL WORK IS TO BE PERFORMED DURING LOW FLOW CONDITIONS AND WORK IS NOT TO BE INITIATED WHEN WEATHER FORECASTS SUGGEST EXTENSIVE RAIN.
5. THE CONSTRUCTION ZONE IS TO BE ISOLATED FROM ADJACENT STREAM FLOWS USING A DAM & PUMP TECHNIQUE AND BY USING ADEQUATE SILT FENCING, STONE OR ANY OTHER METHOD AS APPROVED BY THE CONTRACT ADMINISTRATOR.
6. ALL WORK IS TO BE COMPLETED AS EXPEDITIOUSLY AS POSSIBLE AND ANY WORK THAT HAS BEEN INITIATED MUST BE COMPLETED WITHIN THE WORKING DAY. IF THIS IS NOT POSSIBLE, THEN THE CONTRACTOR MUST ENSURE, TO THE SATISFACTION OF THE CONTRACT ADMINISTRATOR, THAT THE WORK SITE IS ADEQUATELY STABILIZED.


7. ONCE EACH GRADING COMPONENT OF THE PROJECT HAS BEEN COMPLETED BY THE CONTRACTOR, THE SITE IS TO BE REVEGETATED AS PER THE PLANS AND STABILIZED.


. ANY EROSION AND SEDIMENT CONTROLS ARE TO BE REMOVED AT THE COMPLETION OF THE PROJECT AFTER A JOINT INSPECTION BY THE CONTRACTOR AND CONTRACT ADMINISTRATOR.

9. ANY DEVIATIONS FROM THE APPROVED STRATEGY MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.

10. CONTRACTOR TO AVOID ANY UNNECESSARY DISRUPTION OF THE EXISTING CHANNEL

11.SEDIMENT LADEN DEWATERING DISCHARGE SHOULD BE PUMPED TO A SETTLING BASIN OR FILTERING SYSTEM WELL AWAY FROM THE WATERCOURSE AND ALLOWED TO SETTLE AND/OR FILTER THROUGH THE RIPARIAN VEGETATION BEFORE RE-ENTERING THE WATERCOURSE DOWNSTREAM OF THE CONSTRUCTION AREA.





WETLAND RESTOR	RATION SEED MIX
1. SEED MIX BASED ON SEED MIXES SUITABL	E FOR OUR WATERSHED (HCA 2019)
2. SEED MIX TO BE APPLIED AT A RATE OF 22	- 25KG/HA
3. CONTRACTOR TO SOW NURSE CROP OF OA (Fagopyrum esculentum) OVER ENTIRE AREA AT	ATS (Avena sativa) AND BUCKWHEAT A RATE OF 35 KG/HA
4. SEED DISPERSAL METHOD TO BE HAND SEI	EDING AT SPECIFIED RATES


Botanical Name	Common Name	% of mix
Asclepias incarnata ssp. incarnata	Swamp Milkweed	1
Symphyotrichum novae-angliae	New England Aster	1
Symphyotrichum puniceum var. puniceum	Swamp Aster	1
Carex vulpinoidea	Fox Sedge	35
Elymus viginicus var. virginicus	Virginia Wildrye	35
Eutrochium maculatum	Spotted Joe-Pye-Weed	1
Iris versicolor	Harlequin Blue Flag	1
Juncus effusus ssp. solutus	Soft Rush	5
Leersia oryzoides	Rice Cutgrass	1
Mimulus ringens	Square-stemmed Monkeyflower	1
Scirpus atrovirens	Dark-green Bulrush	8
Scirpus cyperinus	Cottongrass Bulrush	1
Verbena hastata	Blue Vervain	9
OTAL		100

UPLAND RESTORATION SEED MIX

1. SEED MIX BASED ON SEED MIXES SUITABLE FOR OUR WATERSHED (HCA 2019) 2. SEED MIX TO BE APPLIED AT A RATE OF 22 - 25KG/HA 3. CONTRACTOR TO SOW NURSE CROP OF OATS (Avena sativa) AND BUCKWHEAT (Fagopyrum esculentum) OVER ENTIRE AREA AT A RATE OF 35 KG/HA


4. SEED DISPERSAL METHOD TO BE HAND SEEDING AT SPECIFIED RATES


Botanical Name	Common Name	% of mix
Oenothera biennis	Common Evening Primrose	25
Anemonastrum canadense	Canada Anemone	1
Asclepias syriaca	Common Milkweed	2
Symphyptrichum cordifolium	Heart Leaved Aster	1
Symphyptrichum novae-angliae	New England Aster	1
Carex granularis	Granular Sedge	15
Clematis virginiana	Virginia Virgin's-bower	1
Elymus virginicus var. virginicus	Virginia Wildrye	40
Euthamia graminifolia	Grass-leaved Goldenrod	1
Monarda fistulosa	Wild Bergamot	1
Rudbeckia hirta	Black-eyed Susan	10
Solidago canadensis	Canada Goldenrod	2
ΓΟΤΑL	-	100





WETLAND PLANT LIST						
KEY	BOTANICAL NAME	COMMON NAME	SIZE	CONT	FLOOD PLAIN QNTY.	
	EMERGENT SPECIES					
sl	Sagittaria latifolia	Common Arrowhead	250cm Ht.	#3cont	292	
ар	Alisma subcordatum	Water Plantain	250cm Ht.	#3cont	292	
as	Sparganium eurycarpum	Common Bur reed	250cm Ht.	#3cont	291	
	TOTAL					
	SUBMERGENT SPECIES					
ес	Elodea canadensis	Common Waterweed	250cm Ht.	#3cont	385	
cd	Nymphaea alba	White Water Lily	250cm Ht.	#3cont	380	
	TOTAL					

PLANT LIST						
Key	Botanical Name	Common Name	Cal. (mm)	Ht. (cm)	Root Condition	MAIN POND
	TREES					
pr	Thuja occidentalis	Eastern White Cedar	60		W.B.	265
ps	Betula alleghaniensis	Yellow Birch	60		W.B.	74
as	Acer saccharinum	Silver Maple	60		W.B.	75
qr	Tilia americana	Basswood	60		W.B.	72
	TOTAL	/				486
	SHRUBS					
nm	Nemopanthus mucronatus	Mountain Holly		60	3 Gal. Pot	309
cs	Cornus stolonifera	Red Osier Dogwood		60	3 Gal. Pot	486
pv	Prunus virginia	Chokecherry		60	3 Gal. Pot	371
ro	Rubus odoratus	Flowering Raspberry		60	3 Gal. Pot	252
seq	Salix exiqua	Sandbar Willow		60	3 Gal. Pot	342
sl	Salix lucida	Shining Willow		60	3 Gal. Pot	224
sp	Salix petiolaris	Slender Willow		60	3 Gal. Pot	256
sc	Sambucus canadensis	Elderberry		60	3 Gal. Pot	427
sa	8pirea alba	Meadowsweet		60	3 Gal. Pot	312
vl	Viburnum lentago	Nannyberry		60	3 Gal. Pot	301
со	Cephalanthus occidentalis	Buttonbush		60	3 Gal. Pot	214
	TOTAL					3494









_		DO NOT CUT LEADER PRUNE AS SPECIFIED
		SUPPORT WIRE AND HOSE AS PER SPECIFICATIONS
		TWO 1.8M T-BARS DRIVEN SECURELY 600MM INTO UNDISTURBED GROUND
-		ROOT CROWN TO BE SET 75MM ABOVE EXISTING GRADE
	-	CUT AND REMOVE $\frac{1}{3}$ OF BURLAP AND AS MUCH OF THE WIRE BASKET. REMOVE ROPES AND TIES. REMOVE ALL SYNTHETIC MATERIAL
		SAUCER 100MM HIGH
		SOIL MIX AS PER SPECIFICATIONS SCARIFY SIDES OF EXCAVATION TREE PIT - 2X WIDTH OF ROOTBALL
-	¥_ - -	ROOTBALL SET ON COMPACTED SOIL MOUND 200MM HIGH

DO NOT CUT LEADER

'BIG O' RODENT COLLAR

SAUCER 100MM HIGH
CUT AND REMOVE $\frac{1}{3}$ OF BURLAP AND AS MUCH OF THE WIRE BASKET REMOVE ROPES AND TIES. REMOVE ALL SYNTHETIC MATERIAL.
SOIL MIX AS PER SPECIFICATIONS
SCARIFY SIDES OF EXCAVATION
ROOTBALL SET ON COMPACTED SOIL MOUND 200MM HIGH

TREE PROTECTION BARRIER: . BARRIER TO BE 1.2m HIGH AND CONSIST OF ORANGE PLASTIC WEB SNOW FENCING ON WOOD FRAME OF 2"X4" S, SUPPORTED ON METAL "T" BARS, 2.0m C/C MAX. 2. WHERE SOME EXCAVATE OR FILL HAS TO BE TEMPORARILY LOCATED NEAR A TREE PROTECTION BARRIER PLYWOOD MUST BE USED TO ENSURE NO MATERIAL ENTERS THE TREE PROTECTION ZONE. 3. LL SUPPORTS AND BRACING SHOULD BE OUTSIDE THE TREE PROTECTION ZONE. ALL SUCH SUPPORTS SHOULD MINIMIZE DAMAGING ROOTS OUTSIDE THE TREE PROTECTION BARRIER. 4. NO CONSTRUCTION ACTIVITY, GRADE CHANGES, SURFACE TREATMENT OR EXCAVATIONS OF ANY KIND IS PERMITTED WITHIN THE TREE PROTECTION ZONE. TREE PROTECTION BARRIER (TYPICAL)

| D14 | N.T.S.

	TRUNK DIAMETER (DBH) ² < 10cm 11 - 40cm	TREE PROTECTION ZONE (TPZ) MINIMUM PROTECTION DISTANCES REQUIRED 1.8m 2.4m	CRITICAL ROOT ZONE (CRZ) DISTANCES REQUIRED 1.8m 4.0m
	41 - 50cm 51 - 60cm 61 - 70cm 71 - 80cm 81 - 90cm	2.4m 3.0m 3.6m 4.2m 4.8m 5.4m	4.0m 5.0m 6.0m 7.0m 8.0m 9.0m
MIN PROTECTION DISTA	91 - 100+cm NCE	6.0m	10.0m

COMMON CATTAIL (Typha latifolia) IS EXPECTED TO SEED IN ON ITS OWN.

SITE REVEGETATION: CONTRACTOR TO MAKE EFFORT TO MINIMIZE SITE DISTURBANCES. ALL DISTURBED AREAS, INCLUDING ACCESS ROUTES, STAGING AREAS AND WORK ZONES ARE TO BE CLEARED (PLANT

MATERIAL TO BE SALVAGED) PRIOR TO CONSTRUCTION AND REVEGETATED WITH OSC 8135

NATIVE PRAIRIE MEADOW SEED MIX AND SALVAGED PLANT MATERIAL UNLESS DIRECTED

WILD RYE (40%) OVER ENTIRE AREA AT A RATE OF 35 KG/HA 1. UPON COMPLETION OF WORK ALL NON-SODDED DISTURBED AREAS ARE TO BE STABILIZED AND RESTORED WITH NATIVE SEED MIX ON 150mm TOPSOIL. 2. SEED DISPERSAL METHOD TO BE DECIDED BY HCA AND APPROVED BY PROJECT MANAGER

SEED MIX BASED ON OSC 8135 NATIVE PRAIRIE MEADOW SEED MIXTURE SUPPLIED BY ONTARIO SEED COMPANY (www.oscseeds.com 519-886-0557) OR APPROVED EQUIVALENT. APPLY AT A RATE OF 22 - 25 KG/HA CONTRACTOR TO SOW NURSE CROP OF OATS (30%), BUCKWHEAT (30%) AND VIRGINIA

1. UPON COMPLETION OF WORK ALL NON-SODDED DISTURBED AREAS ARE TO BE STABILIZED AND RESTORED WITH NATIVE SEED MIX ON 150mm TOPSOIL. 2. SEED DISPERSAL METHOD TO BE DECIDED BY HCA AND APPROVED BY PROJECT MANAGER

SEED MIX TO BE APPLIED AT A RATE OF 22-25KG/HA CONTRACTOR TO SOW NURSE CROP OF OATS (30%), BUCKWHEAT (30%) AND VIRGINIA WILD RYE (40%) OVER ENTIRE AREA AT A RATE OF 35 KG/HA

SEED MIX BASED ON SEED MIX SUITABLE FOR OUR WATERSHED (HCA 2019)

WETLAND SEED MIX NOTES:

UPLAND SEED MIX NOTES:

OTHERWISE BY DESIGN DETAILS.

NOTE

LANDSCAPE NOTES:

1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH BY-LAWS AND CODES HAVING JURISDICTION OVER SITE LOCATION.

2. COMPLETE ALL WORK TO THE SATISFACTION OF THE PROJECT MANAGER. REPORT ANY CHANGES. DISCREPANCIES OR SUBSTITUTIONS TO THE PROJECT MANAGER FOR REVIEW. OBTAIN APPROVAL FROM THE PROJECT MANAGER BEFORE PROCEEDING.

3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE EXISTING SERVICE LOCATIONS.

4. EXACT LOCATIONS OF PLANT MATERIAL WILL BE DETERMINED BY PLACEMENT OF SITE SERVICES SUCH AS HYDRO VAULTS, METERS, UTILITIES ROOF RAIN WATER LEADERS, DRIVEWAYS, LIGHT STANDARDS, ETC.

5. ALL PLANT MATERIAL LOCATIONS TO BE STAKED OR MARKED OUT AND APPROVED BY PROJECT MANAGER PRIOR TO INSTALLATION.

6. SUPPLY ALL PLANT MATERIAL IN ACCORDANCE WITH THE CANADIAN STANDARDS FOR NURSERY STOCK (7TH ED.).

7. INSTALL PLANT MATERIAL ACCORDING TO DETAILS SHOWN.

8. DISTURBED SOIL AREAS AROUND TREES AND SHRUBS ARE TO BE COVERED WITH SHREDDED CONIFER BARK MULCH SUCH AS CANADA RED OR GRO BARK, SPM MULCH, OR APPROVED EQUIVALENT. ALTERNATIVE MULCHES MUST BE APPROVED BY THE PROJECT MANAGER.

9. CONTRACTOR TO UTILIZE LAYOUT DIMENSIONS WHERE PROVIDED. 10.PROVIDE PLANTING BED AREA AS NOTED ON THE DRAWING OR TO

ACCOMMODATE MATURE SIZE OF PLANT MATERIAL. 11. ALL SUPPORT SYSTEMS MUST BE REMOVED TO THE SATISFACTION OF THE

PROJECT MANAGER ONCE THE TREE IS ESTABLISHED. 12. SUPPLY AND PLACE TOPSOIL IN ACCORDANCE WITH OPSS 570 TO A MINIMUM

DEPTH OR 100MM UNLESS OTHERWISE SPECIFIED. 13. SUPPLY AND PLACE SEED IN ACCORDANCE WITH OPSS 572 UNLESS OTHERWISE SPECIFIED.

14. CONTRACTOR TO PROVIDE NECESSARY EROSION CONTROL PROTECTION AS REQUIRED TO ENSURE SOIL STABILIZATION AND PROPER SEED GERMINATION. 15. ALL DIMENSIONS IN MM UNLESS OTHERWISE NOTED.

16.IF DISCREPANCIES ARISE BETWEEN PLANT MATERIAL COUNT SHOWN ON

DRAWING AND PLANT LIST THE DRAWING SHALL BE CONSIDERED CORRECT.

17. CONTRACTOR TO PROVIDE MINIMUM 2 YEAR WARRANTY FROM DATE ACCEPTED ON ALL WORK UNLESS OTHERWISE SPECIFIED.

18. ANY SITE PLAN OR GRADING AND SERVICING SHOWN IS FOR INFORMATION ONLY. REFER TO APPROVED DRAWINGS.

ISSUED FOR TENDER 20241025 EEG REVISED BASED ON HCA COMMENTS 20241018 EEG 20240208 EEG REVISED BASED ON HCA COMMENTS REVISED BASED ON HCA COMMENTS 20201204 EEG DATE BY REVISIONS DATE October 25, 2024 SCALE CONSULTANT Hamilton Conservation Authority A Healthy Watershed for Everyone SALTFLEET CONSERVATION AREA STONEY CREEK (SC-8) PLANTING PLAN DETAILS PROJECT No DESIGN EEG 19028

SHEET No.

16

CHECKED

EG